AMENDMENT OF SOLICITATION/MODIFICATION OF CONTRACT	1. CONTRACT ID CODE	PAGE 1 OF 2 PAGES

2. AMENDMENT/MODIFICATION NO.	3. EFFECTIVE DATE	4. REQUISITION/PURCHASE REQ. NO.	5. PROJECT NO. *(If applicable)*
A001	See Block 16C		

6. ISSUED BY CODE	7. ADMINISTERED BY *(If other than Item 6)* CODE
U.S. Embassy Ottawa **General Services Office** **P.O. Box 866, Station B** **Ottawa, ON K1P 5T1**	

8. NAME AND ADDRESS OF CONTRACTOR *(NO., street,city,county,State,and ZIP Code)*	X	9a. AMENDMENT OF SOLICITATION NO. **SCA52516Q0028**
		9b. DATED *(SEE ITEM 11)* **August 8, 2016**
		10a. MODIFICATION OF CONTRACT/ORDER NO.
		10b. DATED *(SEE ITEM 13)*

11. **THIS ITEM ONLY APPLIES TO AMENDMENTS OF SOLICITATIONS**

[X] The above numbered solicitation is amended as set forth in Item 14. The hour and date specified for receipt of Offers

[ ] is extended, [X] is not extended

Offers must acknowledge receipt of this amendment prior to the hour and date specified in the solicitation or as amended, by one of the following methods: (a) By completing Items 8 and 15, and returning **1** copies of the amendment;(b) By acknowledging receipt of this amendment on each copy of the offer submitted; or© By separate letter or telegram which includes a reference to the solicitation and amendment numbers.

FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE DESIGNATED FOR THE RECEIPT OF OFFERS PRIOR TO THE HOUR AND DATE SPECIFIED MAY RESULT IN REJECTION OF YOUR OFFER. If by virtue of this amendment you desire to change an offer already submitted, such change may be made by telegram or letter, provided each telegram or letter makes reference to the solicitation and this amendment, and is received prior to the opening hour and date specified.

12. **ACCOUNTING AND APPROPRIATION DATA** *(If required)*

13. **THIS ITEM APPLIES ONLY TO MODIFICATIONS OF CONTRACTS/ORDERS, IT MODIFIES THE CONTRACT/ORDER NO. AS DESCRIBED IN ITEM 14.**

	A. THIS CHANGE ORDER IS ISSUED PURSUANT TO: *(Specify authority)* THE CHANGES SET FORTH IN ITEM 14 ARE MADE IN THE CONTRACT ORDER NO. IN ITEM 10A.
	B. THE ABOVE NUMBERED CONTRACT/ORDER IS MODIFIED TO REFLECT THE ADMINISTRATIVE CHANGES *(such as changes in paying office, appropriation date, etc.)* SET FORTH IN ITEM 14, PURSUANT TO THE AUTHORITY OF FAR 43.103(b)
	C. THIS SUPPLEMENTAL AGREEMENT IS ENTERED INTO PURSUANT TO AUTHORITY OF:
	D. OTHER *(Specify type of modification and authority)*

E. **IMPORTANT:** Contractor [ ] is not, [ ] is required to sign this document and return ____ copies to the issuing office.

14. **DESCRIPTION OF AMENDMENT/MODIFICATION** *(Organized by UCF section headings, including solicitation/contract subject matter where feasible.)*

RFQ No. SCA52516Q0028, Pollinator Garden for the U.S. Embassy Chancery Office Building

The purpose of this amendment is to reflect changes as follows:

1) Attachment 3, Specifications, Section 3.3, is hereby amended to include work requirements under Section 3.3.10 and shall read as follows:

- next page -

Except as provided herein, all terms and conditions of the document referenced in Item 9A or 10A, as heretofore changed, remains unchanged and in full force and effect.

15A. NAME AND TITLE OF SIGNER *(Type or print)*		16A. NAME OF CONTRACTING OFFICER **IRENE HARRISON**	
15B. NAME OF CONTRACTOR/OFFEROR BY *(Signature of person authorized to sign)*	15C.DATE SIGNED	16B. UNITED STATES OF AMERICA BY *(Signature of Contracting Officer)*	16C.DATE SIGNED 8/26/16

Standard Form 30

3.3 The Contractor shall perform the following work requirements:

3.3.1 Be responsible to have utility locates done prior to execution.

3.3.2 Excavate and remove sod and topsoil to depth of 300mm.

3.3.3 Remove existing irrigation. Salvage for new irrigation installation.

3.3.4 Relocate, design and supply new irrigation system.

3.3.5 Add 300mm of new garden soil and 75mm of compost. Till compost into top 150mm of soil.

3.3.6 A sample of the new garden soil shall be tested prior to the installation of the plant life. The Contractor if required, shall adjust soil condition to promote the growth of plant life of the new garden.

3.3.7 Supply a copy of the soil test result with the required correction to adjust soil growth condition.

3.3.8 Supply and install shredded pine mulch to the bed prior to completion and shall be installed to the desired depth in accordance with the detailed drawings.

3.3.9 Walkway shall be done by others.

3.3.10 Add 18" wide filter fabric. Install around the lawn light black plastic edging to retain the river wash stone and drought resistant flowers. Refer to the attached revised landscape layout.

2) Attached drawings are provided for offerors' reference.
   - Revised landscape plan and planting plan. Revision includes walkway and lighting location with plant alteration around existing lighting.
   - Current irrigation plan and electrical layout.

3) The submission due date and time of September 9, 2016, no later than 4:00 P.M. remains the same.

4) All other terms and conditions remain in full force and effect.